

BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/03/2020-21 Dated: 24-07-2020

APPROVED TENDER SCHEDULE -'B'

Item 21

Name of Work :-Improvements to parks at Judicial layout in ward no 04 of yelahanka Satellite town sub division

SI	Description	Unit	Approved Qty	Rate quoted by the contractor approved rates Sri KEERTHI N	
				Rate	Rate in Words
1	KSRB 2-2 : Earthwork excavation by manual means for foundation of buildings, water supply and sanitary lines and electrical conduits etc, either in pits or in trenches 1.5m and above in width, in soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. including breaking of clods complete as per specifications. (Page No 6, I.No.2.3)	Cum	240.00	394.42	Three Hundred NinetyFour Paise FortyTwo Only
2	KSRRB M2100-10. Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. (P.No-222,I No-27.18)	Cum	2.00	5421.90	Five Thousand Four Hundred TwentyOne Paise Ninety Only
3	KSRB 4-1.6 ; Providing and laying in position plain cement concrete of Mix 1:2:4 with OPC @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.53cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No-13,I No-4.6)	Cum	3.24	5747.32	Five Thousand Seven Hundred FortySeven Paise ThirtyTwo Only

	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation etc., complete. As per the direction of Engineer incharge. (P.No.27, I.No.5.30)	Nos	333.00	432.48	Four Hundred ThirtyTwo Paise FortyEight Only
5	Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8 Specification No. KSRRB M800-6. (P.No.180, I.No.24.1 of PW, P&IWTD SR 2018-19)	Sqm	30.00	84.80	EightyFour Paise Eighty Only
6	KSRRB 2.6 Providing and filling sand in trenches to required depth including watring ramming with all leads and lift complete as per specifications and directed by the engineer incharge at the site (P-7 I N-2.13 SR 2018-19)	Cum	187.50	2183.60	Two Thousand One Hundred EightyThree Paise Sixty Only
7	Supply and fixing of children Play Equipment Curved structural posts of height 3.5m, and 2.7mare to be schedule HOT DIP Galvanized steel with a 114mm ODand 2.2mm (wall) thickness of the tubing. The polesare welded on to a base plate made from steel with 114mm inner diameter. Handrail Dia 60mm shall bean all-robotic welded unit, fabricated from galvanized steel pipes with a baked on powder coating [using AkzoNobel INTERPON paints]finish. Swing of size 3.3 m x 0.9 m, Spring twirlof size 2.8mx 1.6 m, Twirl of size 3.0 m x 0.7 m, Steering wheel loops of size 2.5 m x 0.5 m are all robotic welded fabricated from 32 O.D. galvanized steel pipes for the outer pipes and 25mm O.D. galvanized steel for the inner parallel bars with a baked on powder coat finish. Bolts, nuts, screws, washers and etc used for assembly shall be stainless steel 304 of tamper resistant stainless steel. Exposed hardware shall be covered with ultra violet stabilized plastic safety caps as per EN1176 standards as a safety feature against protruding hardware, aesthetic pleasing against ugly exposed hardware	Each	1.00	1498833.00	Fourteen Lakh NinetyEight Thousand Eight Hundred ThirtyThree Only

Supply and fixing of children Play Equipment Fiero A Swing : Shaped structural posts of height 2.31 m to be schedule HOT DIP Galvanized steel with a 114mm OD and 2.2mm (wall) thickness of the tubing. Plastic Components such as swing seats [super thick plastic] shall be animated and shall be rotationally molded from antistatic, copolymer, virgin linear low density UV stabilized polyethylene, with color molded in and minimum thickness of 6 - 8mm. The rates are to be inclusive of supply and installation at site. Inclusive of All Taxes and Transportation Charges (Data approved rate)	Each	1.00	126892.00	One Lakh TwentySix Thousand Eight Hundred NinetyTwo Only
9 Supply and fixing of children Play Equipment Two seater seesaw : The See Saw consists of 2 poles of Dia 114mm and thickness of 2.5mm which balances the horizontal rod at the center which is of size 3110 mm length and Dia 114 mm. It consists of 2 seats which is made of LLDPE virgin plastic of size 305mm X 213 mm X 125 mm. The rates are to be inclusive of supply and installation at site. Inclusive of All Taxes and Transportation Charges (Data approved rate)	Each	1.00	83478.00	EightyThree Thousand Four Hundred SeventyEight Only

Signature of the Contractor

N. Keshav

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.